



# Mallard, Inc.

**QUARTERLY WATER SAMPLING REPORT  
CITY OF DUNEDIN  
MUNICIPAL SERVICES FACILITY  
750 MILWAUKEE AVENUE  
DUNEDIN, FLORIDA**

**JANUARY 13, 2011**



# Mallard, Inc.

January 13, 2011

Mr. Kevin Bagnall  
K.B. Industries, Inc.  
28100 U.S. Highway 19 North  
Suite 410  
Clearwater, Florida 33761

3296 Main Street  
Cottondale, Florida 32431  
(850) 352-2299 • Fax (850) 352-2239

10801 N. Newport Avenue  
Tampa, Florida 33612  
(813) 935-2073 • Fax (813) 935-3106

**RE: Fourth Quarter Water Sampling Activities at the City of Dunedin Municipal Services Facility, 750 Milwaukee Avenue, Dunedin, Florida.**

Dear Mr. Bagnall:

Mallard, Inc. (Mallard) has recently completed quarterly water sampling activities for the referenced project. This report summarizes the results for the activities conducted with the KBI Industries Flexi-Pave product.

## **Project Understanding**

Mallard is of the understanding that KBI is interested in determining how the nitrate and phosphorous loads in surface water would be affected subsequent to percolation through the Flexi-Pave product into the underlying groundwater. The Flexi-Pave product is a porous material that contains interstitial pore spaces that allow for the percolation of water and the accumulation and growth of bacteria. The objective of this experiment was to determine what, if any, reductions in nitrate and phosphorous concentrations result from the use of the Flexi-Pave product.

## **Field Activities**

Two new load-bearing parking spaces were installed using the Flexi-Pave product at the Municipal Services Building in Dunedin, Florida. Immediately prior to the Flexi-Pave product being installed, Mallard installed a total of four permanent water-capture systems at different locations along the edge of the parking spaces. The water-capture system locations are indicated on the attached map. A pvc pipe was installed at an approximate 45 degree angle to insure the piping would access the water-capture basin located immediately beneath the Flexi-Pave product and sub-base materials, but above the existing water table. A schematic of the water-capture system is attached. Specifically, the water-capture systems consist of a 2-foot long sch 40 pvc pipe that is 12" in diameter and capped only at the bottom. The open end of the pipe faces upward and the pipe was filled with coarse sand to facilitate capture and temporary retention of water. Holes were drilled in the bottom cap of the pipe to allow for drainage. A 1" diameter pvc pipe with a one-foot section of screen (0.01" slot) was placed inside the sand-filled pipe at an angle. The 1" pipe was placed inside a 2" diameter protective casing up to land surface. The top of the 1" diameter pipe was accessed at ground level from within a 12" x 17" flush-mounted sprinkler box. The water-capture systems were installed manually by Mallard personnel. Upon initial water testing through the Flexi-Pave product and into the water-capture systems, it was determined that quicker percolation rates could be achieved by replacing the coarse sand in the pvc cylinder with 57# rock material, and extending the cylinder up to the approximate bottom of the Flexi-Pave product to eliminate fluid loss from horizontal flow through the sub-base.

Two water-capture systems (WCS-1 and WCS-2) were installed beneath a section of the parking space with a stabilized load bearing sub-base, and capped with the Flexi-Pave product. WCS-1 was used as a control system. The third system (WCS-3) was installed beneath a section of the parking space with a water treatment residual (WTR) in place, then followed by the stabilized load bearing sub-base, and then the Flexi-Pave product. The fourth system (WCS-4) was installed beneath a section of the parking space that has a WTR in place on top of a thin textile material layer, followed by the stabilized load bearing sub-base, and then the Flexi-Pave product. Individual schematics for each water-capture system are attached. The use of a stabilized load-bearing sub-base capped by the two inches of Flexi-Pave is the standard application protocol for a load-bearing parking lot. The water-capture systems were installed beneath these three different sections of the parking spaces to test the ability of the Flexi-Pave product to reduce the concentrations of nitrates and phosphorous found in surface water flows.

On December 21, 2010, Mallard collected a set of water samples from three of the four systems for analysis (WCS-1, WCS-3 and WCS-4). Mallard poured known concentration standards of Nitrogen (2.4 mg/L) and Total Phosphorous (19 mg/L) onto the Flexi-Pave surface above each water-capture system and allowed it to percolate through into the system. The water samples collected were tested for nitrates by EPA Method 353.2 and total phosphorous by EPA Method 365.4. The samples were tested by a state certified analytical laboratory. The results of these samples were used to determine what the sub-base materials contribute to the phosphorous and nitrate concentrations (if any). The results of the water samples are summarized on Table 1. The results for nitrates indicate that nitrate was detected at concentrations of 0.40 mg/L, 0.51 mg/L and 1.9 mg/L at locations WCS-1, WCS-3 and WCS-4, respectively. The nitrate standard used was 2.4 mg/L. This data indicates an 83% reduction in nitrate concentration at WCS-1, a 79% reduction in nitrate concentration at WCS-3 and a 21% reduction in nitrate concentration at WCS-4 subsequent to the nitrate standard percolating through the flexi-pave materials.

The results for total phosphorous indicate that total phosphorous was detected at concentrations of 2.3 mg/L, 1.4 mg/L and 3.7 mg/L at locations WCS-1, WCS-3 and WCS-4, respectively. The total phosphorous standard used was 19 mg/L. This data indicates an 88% reduction in phosphorous concentration at WCS-1, a 92.6% reduction in phosphorous concentration at WCS-3 and an 81% reduction in phosphorous concentration at WCS-4 subsequent to the total phosphorous standard percolating through the flexi-pave materials.

These results also indicate a decrease in nitrate and total phosphorous concentrations since March 3, 2010, when samples were also collected from WCS-1, WCS-3 and WCS-4 using known nitrate (2.4 mg/L) and total phosphorous (20 mg/L) standards (Table 1).


These results indicate what impacts each variation of the Flexi-Pave product has on nitrates and total phosphorous prior to reaching the groundwater table. These results indicate that the Flexi-Pave product is effective in reducing nitrate loads to the groundwater table over time in the differently constructed sub-bases for WCS-1 (standard construction) and WCS-3 (WTR). However, the construction of WCS-4 (WTR plus textile layer) does not appear to have any significant influence in reducing nitrate loads over time. This is based on the nitrate concentrations showing a 66% reduction in March, 2010, but only a 21% reduction in December 2010.

The Flexi-Pave product appears to be effective in reducing the total phosphorous loads to the groundwater over time at each of the WCS-1, WCS-3 and WCS-4 sample locations. This is based on the total phosphorous concentrations showing a 30% to 35% reduction in March, 2010, and 88%, 92.6% and 81% reductions, respectively, in December 2010.


Should you have any questions concerning this report, please do not hesitate to contact me at (813) 935-2073.

Sincerely,  
**Mallard, Inc.**

*Maura Clark* 1/13/11  
Maura Clark, P.G.  
Vice President  
Florida License No. 1621



## **FIGURES**




NOT TO SCALE



**Mallard, Inc.**

**WATER CAPTURE SYSTEM #1, #2**




NOT TO SCALE



**Mallard, Inc.**

**WATER CAPTURE SYSTEM #3**



NOT TO SCALE




**Mallard, Inc.**

**WATER CAPTURE SYSTEM #4**



W O O D   A V E N U E





SIDEWALK



FLEXI-PAVE  
PARKING SPACE

ASPHALT  
PARKING SPACE

FLEXI-PAVE  
PARKING SPACE



0 5  
APPROXIMATE SCALE  
(FEET)

A horizontal scale bar with a black and white alternating pattern, marked with '0' at the left end and '5' at the right end.



**Mallard, Inc.**

**WATER CAPTURE SYSTEM LOCATION MAP  
DUNEDIN, FLORIDA**

## **LABORATORY DATA REPORT**

## ANALYTICAL REPORT

Job Number: 660-38920-1  
Job Description: Dunedin Public Works

For:  
Mallard, Inc.  
10801 N. Newport Avenue  
Tampa, FL 33612  
Attention: Maura Clark



Approved for release.  
Amy Atkins  
Project Manager I  
12/30/2010 11:43 AM

---

Amy Atkins  
Project Manager I  
amy.atkins@testamericainc.com  
12/30/2010

Methods: FDEP, DOH Certification #: Tampa E84282. These test results meet all the requirements of NELAC unless specified in the case narrative. All questions regarding this test report should be directed to the TestAmerica Project Manager who signed this test report. The estimated uncertainty associated with these reported results is available upon request. The results contained in this test report relate only to these samples included herein.

**Job Narrative**  
**660-38920-1**

**Receipt**

All samples were received in good condition within temperature requirements.

**General Chemistry**

Method 365.4: The matrix spike(MS) recovery for batch 104653 was outside control limits. The associated laboratory control sample (LCS) recovery met acceptance criteria.

## EXECUTIVE SUMMARY - Detections

Client: Mallard, Inc.

Job Number: 660-38920-1

Lab Sample ID Analyte	Client Sample ID	Result / Qualifier	Reporting Limit	Units	Method
<b>660-38920-1</b>	<b>WCS-1</b>				
Nitrate as N		0.40	0.50	mg/L	353.2
Phosphorus, Total		2.3	0.30	mg/L	365.4
<b>660-38920-2</b>	<b>WCS-3</b>				
Nitrate as N		0.51	0.50	mg/L	353.2
Phosphorus, Total		1.4	0.30	mg/L	365.4
<b>660-38920-3</b>	<b>WCS-4</b>				
Nitrate as N		1.9	0.50	mg/L	353.2
Phosphorus, Total		3.7	0.30	mg/L	365.4

## METHOD SUMMARY

Client: Mallard, Inc.

Job Number: 660-38920-1

<b>Description</b>	<b>Lab Location</b>	<b>Method</b>	<b>Preparation Method</b>
<b>Matrix: Water</b>			
Nitrogen, Nitrate-Nitrite	TAL TAM	MCAWW 353.2	
Phosphorus, Total	TAL TAM	EPA 365.4	
Phosphorus, Total	TAL TAM		MCAWW 365.2/365.3/365

### Lab References:

TAL TAM = TestAmerica Tampa

### Method References:

EPA = US Environmental Protection Agency

MCAWW = "Methods For Chemical Analysis Of Water And Wastes", EPA-600/4-79-020, March 1983 And Subsequent Revisions.

## METHOD / ANALYST SUMMARY

Client: Mallard, Inc.

Job Number: 660-38920-1

<b>Method</b>	<b>Analyst</b>	<b>Analyst ID</b>
MCAWW 353.2	Sengsouvana, Dom	DS
EPA 365.4	Office, Trey	TO

## SAMPLE SUMMARY

Client: Mallard, Inc.

Job Number: 660-38920-1

<b>Lab Sample ID</b>	<b>Client Sample ID</b>	<b>Client Matrix</b>	<b>Date/Time Sampled</b>	<b>Date/Time Received</b>
660-38920-1	WCS-1	Water	12/21/2010 1157	12/21/2010 1400
660-38920-2	WCS-3	Water	12/21/2010 1253	12/21/2010 1400
660-38920-3	WCS-4	Water	12/21/2010 1206	12/21/2010 1400



Client: Mallard, Inc.

Job Number: 660-38920-1

---

General Chemistry

Client Sample ID: **WCS-1**

Lab Sample ID: 660-38920-1

Date Sampled: 12/21/2010 1157

Client Matrix: Water

Date Received: 12/21/2010 1400

Analyte	Result	Qual	Units	MDL	PQL	Dil	Method
Nitrate as N	0.40	I	mg/L	0.10	0.50	1.0	353.2
	Analysis Batch: 660-104481	Date Analyzed: 12/21/2010	1900				
Phosphorus, Total	2.3		mg/L	0.10	0.30	1.0	365.4
	Analysis Batch: 660-104653	Date Analyzed: 12/29/2010	1114				
	Prep Batch: 660-104577	Date Prepared: 12/28/2010	1300				

Client: Mallard, Inc.

Job Number: 660-38920-1

---

General Chemistry

Client Sample ID: **WCS-3**

Lab Sample ID: 660-38920-2

Date Sampled: 12/21/2010 1253

Client Matrix: Water

Date Received: 12/21/2010 1400

Analyte	Result	Qual	Units	MDL	PQL	Dil	Method
Nitrate as N	0.51		mg/L	0.10	0.50	1.0	353.2
	Analysis Batch: 660-104481	Date Analyzed: 12/21/2010	1900				
Phosphorus, Total	1.4		mg/L	0.10	0.30	1.0	365.4
	Analysis Batch: 660-104653	Date Analyzed: 12/29/2010	1114				
	Prep Batch: 660-104577	Date Prepared: 12/28/2010	1300				

Client: Mallard, Inc.

Job Number: 660-38920-1

---

General Chemistry

Client Sample ID: **WCS-4**

Lab Sample ID: 660-38920-3

Date Sampled: 12/21/2010 1206

Client Matrix: Water

Date Received: 12/21/2010 1400

Analyte	Result	Qual	Units	MDL	PQL	Dil	Method
Nitrate as N	1.9		mg/L	0.10	0.50	1.0	353.2
	Analysis Batch: 660-104481	Date Analyzed: 12/21/2010	1900				
Phosphorus, Total	3.7		mg/L	0.10	0.30	1.0	365.4
	Analysis Batch: 660-104653	Date Analyzed: 12/29/2010	1114				
	Prep Batch: 660-104577	Date Prepared: 12/28/2010	1300				

## DATA REPORTING QUALIFIERS

Client: Mallard, Inc.

Job Number: 660-38920-1

<b>Lab Section</b>	<b>Qualifier</b>	<b>Description</b>
General Chemistry		
	J3	Estimated value; value may not be accurate. Spike recovery or RPD outside of criteria.
	U	Indicates that the compound was analyzed for but not detected.
	I	The reported value is between the laboratory method detection limit and the laboratory practical quantitation limit.

## Quality Control Results

Client: Mallard, Inc.

Job Number: 660-38920-1

### Method Blank - Batch: 660-104481

**Method: 353.2**  
**Preparation: N/A**

Lab Sample ID: MB 660-104481/1  
Client Matrix: Water  
Dilution: 1.0  
Date Analyzed: 12/21/2010 1900  
Date Prepared: N/A

Analysis Batch: 660-104481  
Prep Batch: N/A  
Units: mg/L

Instrument ID: LACHAT  
Lab File ID: N/A  
Initial Weight/Volume: 1.0 mL  
Final Weight/Volume: 10 mL

Analyte	Result	Qual	MDL	PQL
Nitrate Nitrite as N	0.10	U	0.10	0.50
Nitrite as N	0.10	U	0.10	0.50
Nitrate as N	0.10	U	0.10	0.50

### Lab Control Sample - Batch: 660-104481

**Method: 353.2**  
**Preparation: N/A**

Lab Sample ID: LCS 660-104481/2  
Client Matrix: Water  
Dilution: 1.0  
Date Analyzed: 12/21/2010 1900  
Date Prepared: N/A

Analysis Batch: 660-104481  
Prep Batch: N/A  
Units: mg/L

Instrument ID: LACHAT  
Lab File ID: N/A  
Initial Weight/Volume: 1.0 mL  
Final Weight/Volume: 10 mL

Analyte	Spike Amount	Result	% Rec.	Limit	Qual
Nitrate Nitrite as N	1.00	0.941	94	90 - 110	
Nitrite as N	0.997	0.984	99	90 - 110	

## Quality Control Results

Client: Mallard, Inc.

Job Number: 660-38920-1

**Matrix Spike/  
Matrix Spike Duplicate Recovery Report - Batch: 660-104481**

**Method: 353.2  
Preparation: N/A**

MS Lab Sample ID: 660-38909-A-1 MS  
Client Matrix: Water  
Dilution: 1.0  
Date Analyzed: 12/21/2010 1900  
Date Prepared: N/A

Analysis Batch: 660-104481  
Prep Batch: N/A

Instrument ID: LACHAT  
Lab File ID: N/A  
Initial Weight/Volume: 1.0 mL  
Final Weight/Volume: 25 mL

MSD Lab Sample ID: 660-38909-A-1 MSD  
Client Matrix: Water  
Dilution: 1.0  
Date Analyzed: 12/21/2010 1900  
Date Prepared: N/A

Analysis Batch: 660-104481  
Prep Batch: N/A

Instrument ID: LACHAT  
Lab File ID: N/A  
Initial Weight/Volume: 1.0 mL  
Final Weight/Volume: 25 mL

Analyte	% Rec.		Limit	RPD	RPD Limit	MS Qual	MSD Qual
	MS	MSD					
Nitrate Nitrite as N	95	94	90 - 110	1	30		
Nitrite as N	103	103	90 - 110	0	30		

**Quality Control Results**

Client: Mallard, Inc.

Job Number: 660-38920-1

**Method Blank - Batch: 660-104577**

Lab Sample ID: MB 660-104577/10-A  
 Client Matrix: Water  
 Dilution: 1.0  
 Date Analyzed: 12/29/2010 1114  
 Date Prepared: 12/28/2010 1300

Analysis Batch: 660-104653  
 Prep Batch: 660-104577  
 Units: mg/L

**Method: 365.4  
 Preparation: 365.2/365.3/365**

Instrument ID: SEAL1  
 Lab File ID: N/A  
 Initial Weight/Volume: 20 mL  
 Final Weight/Volume: 20 mL

Analyte	Result	Qual	MDL	PQL
Phosphorus, Total	0.10	U	0.10	0.30

**Lab Control Sample - Batch: 660-104577**

Lab Sample ID: LCS 660-104577/11-A  
 Client Matrix: Water  
 Dilution: 1.0  
 Date Analyzed: 12/29/2010 1114  
 Date Prepared: 12/28/2010 1300

Analysis Batch: 660-104653  
 Prep Batch: 660-104577  
 Units: mg/L

**Method: 365.4  
 Preparation: 365.2/365.3/365**

Instrument ID: SEAL1  
 Lab File ID: N/A  
 Initial Weight/Volume: 20 mL  
 Final Weight/Volume: 20 mL

Analyte	Spike Amount	Result	% Rec.	Limit	Qual
Phosphorus, Total	1.00	1.10	110	90 - 110	

**Matrix Spike/  
 Matrix Spike Duplicate Recovery Report - Batch: 660-104577**

**Method: 365.4  
 Preparation: 365.2/365.3/365**

MS Lab Sample ID: 660-38954-A-2-B MS  
 Client Matrix: Water  
 Dilution: 1.0  
 Date Analyzed: 12/29/2010 1114  
 Date Prepared: 12/28/2010 1300

Analysis Batch: 660-104653  
 Prep Batch: 660-104577

Instrument ID: SEAL1  
 Lab File ID: N/A  
 Initial Weight/Volume: 20 mL  
 Final Weight/Volume: 20 mL

MSD Lab Sample ID: 660-38954-A-2-C MSD  
 Client Matrix: Water  
 Dilution: 1.0  
 Date Analyzed: 12/29/2010 1114  
 Date Prepared: 12/28/2010 1300

Analysis Batch: 660-104653  
 Prep Batch: 660-104577

Instrument ID: SEAL1  
 Lab File ID: N/A  
 Initial Weight/Volume: 20 mL  
 Final Weight/Volume: 20 mL

Analyte	% Rec.		Limit	RPD	RPD Limit	MS Qual	MSD Qual
	MS	MSD					
Phosphorus, Total	111	99	90 - 110	9	30	J3	

**TestAmerica Tampa**  
 6712 Benjamin Road Suite 100  
 Tampa, FL 33634  
 Phone (813) 885-7427 Fax (813) 885-7049

660-38920

**Chain of Custody Record**

**TestAmerica**  
 4715 Lake Dr. Fort Lauderdale, FL 33309

**Client Information**  
 Client Contact: Maura Clark Sampler: Maura Clark Lab Pk: Atkins, Amy  
 Phone: 813-935-2073 E-Mail: amy.atkins@testamericainc.com  
 Company: Mallard, Inc. Carrier Tracking No(s): 660-32963.1

Address: 10801 N. Newport Avenue Due Date Requested: \_\_\_\_\_  
 City: Tampa TAT Requested (days): \_\_\_\_\_  
 State, Zip: FL, 33612  
 Phone: 813-935-2073 PO #: \_\_\_\_\_  
 Email: fiduck@verizon.net Project #: 66003333  
 Project Name: Dunedin SSOV#: \_\_\_\_\_  
 Site: Dunedin Public Works

Sample Identification	Sample Date	Sample Time	Sample Type (C=C-comp, G=grab)	Matrix (W=water, S=solid, O=overhead, G=grab, BT= tissue, AA=air)	Field Filtered Sample (Yes or No)		Perform MS/MSD (Yes or No)		Total Number of containers	Special Instructions/Note:
					S	N	S	N		
WCS-1	12/21/10	1157	G	Water	X	X			2	
WCS-3	12/21/10	1253	G	Water	X	X			2	
WCS-4	12/21/10	1206	G	Water	X	X			2	

**Possible Hazard Identification**  
 Non-Hazard  Flammable  Skin Irritant  Poison B  Unknown  Radiological

Deliverable Requested: I, II, III, IV, Other (specify) \_\_\_\_\_

Empty Kit Relinquished by: AT Luck Date: 12-17-10 Time: 1700  
 Relinquished by: Maura Clark Date/Time: 12/21/10 1400 Company: Mallard  
 Relinquished by: \_\_\_\_\_ Date/Time: \_\_\_\_\_ Company: \_\_\_\_\_  
 Relinquished by: \_\_\_\_\_ Date/Time: \_\_\_\_\_ Company: \_\_\_\_\_

Custody Seals Intact:  Yes  No Custody Seal No.: 470 C 2407

Received by: Amara Chavis Date/Time: 12/21/10 1400 Company: TTT  
 Received by: \_\_\_\_\_ Date/Time: \_\_\_\_\_ Company: \_\_\_\_\_

Method of Shipment: CPD Date/Time: \_\_\_\_\_ Company: \_\_\_\_\_

Special Instructions/OC Requirements: \_\_\_\_\_

Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)  
 Return To Client  Disposal By Lab  Archive For \_\_\_\_\_ Months

COOLING TEMPERATURE(S) °C and Other Remarks: \_\_\_\_\_



## Login Sample Receipt Check List

Client: Mallard, Inc.

Job Number: 660-38920-1

**Login Number: 38920**

**List Source: TestAmerica Tampa**

**Creator: Harrison, Amanda**

**List Number: 1**

Question	T / F / NA	Comment
Radioactivity either was not measured or, if measured, is at or below background	N/A	
The cooler's custody seal, if present, is intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	4.7 degrees C Cu-07
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the sample IDs on the containers and the COC.	True	
Samples are received within Holding Time.	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
VOA sample vials do not have headspace or bubble is <6mm (1/4") in diameter.	N/A	
If necessary, staff have been informed of any short hold time or quick TAT needs	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	